



# Khunbu Pasanglhamu Rural Municipality

Office of the Rural Municipal Executive

Chaurikharka, Solukhumbu

## Bill of Quantity

आयोजनाको नाम: खुन्दे स्ट्रीट लाईट जडान गर्ने कार्य

स्थल: खु पा गा पा - ०४, खुन्दे

F/Y:82/83

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
1	Providing & Instalation of Project Signboard	Nos	1.00			
2	Excavation in BMS including 30m lead & 1.5m lift per m3	Cu.M	3.00			
3	Earth work in Back filling for foundatin and pipe trench including 30m lead & 1.5m lift per m3	Cu.M	0.32			
4	Dry Stone solling and Dry stone filling work in Floor foundation including & 1.5m lift per m3	Cu.M	1.00			
5	PCC (1:3:6) for street light pole	Cu.M	1.20			
6	Formworks	Sq.M	15.12			
7	MS Base Plate (20cm*20cm*3 mm)	KG	18.84			
8	MS pole 5.5m high with rust proof Hot Deep Galvanization dimension 65mm for buttom 2.5 m 50mm for top 2.5 m	KG	301.70			
9	Ms light Arm Set with Nut Bolts Acording to specification Of Site Engineer	set	20.00			

Khumla Pasanglhamu Rural Municipality

Office of the Rural Municipal Executive  
Chaurikharka, Solukhumbu

Bill of Quantity

आयोजनाको नाम: खुन्दे स्ट्रीट लाईट जडान गर्ने कार्य  
स्थल: खु पा गा पा - ०४, खुन्दे

F/Y:82/83

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
10	Solar Strret light 40W -12V DC with auto Dimming System (Sensors)	Set	20.00			
11	Trasportation and all Complete Fitting Work	KG	310.00			
Total amount						
VAT@13%						
Total Project Cost						

Total in words:

Name of firm

Address

Signature

Seal of Firm