



ॐ श्री गणेशाय नमः

खुम्बु पासाङलाम गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
चौरीखोला, खुम्बु
कोशी प्रदेश, नेपाल



प.सं.: ०८२/०८३
च.नं. १६४३


मिति:- २०८३।०२।०४

विषय :- दरभाउपत्र पेश गर्ने बारे ।

श्री सबै निर्माण ब्यावसायीहरु

यस गाउँपालिकाबाट चालु आ.व. २०८२।०८३ मा यसै पत्र साथ संलग्न BOQ मा उल्लिखित आइटमका कार्यहरु गर्नु पर्ने भएकाले उक्त कार्य त्यस फर्मबाट के, कति दर रेटमा उपलब्ध गराउन सकिन्छ? तीन (०३) दिन भित्र यस कार्यालयमा दर भाउपत्र पेश गर्नु हुन अनुरोध छ ।

| कामको विवरण | कार्यान्वयन हुने वडा | टोल |
|--|----------------------|------------------|
| मिस्लुङ नाम्चे स्ट्रीट लाईट जडान गर्ने कार्य | | ५ मिस्लुङ नाम्चे |


सुजन कुमार बुढाथोकी
प्रशासकीय अधिकृत

Khumbu Pasanglhamu Rural Municipality
Office of the Rural Municipal Executive
Chaurikharka, Solukhumbu
Bill of Quantity

FY:82/83

Name of the Project : Mislung Namche Street Light Jadan
Location of the Project:- Khumbu Pasanglhamu R.M.-5, Mislung

| S.N. | Description of work | Unit | Estimated Quantity | Rate (NRs.) excluding Vat | | Amount (NRs.) excluding Vat |
|------|--|------|--------------------|---------------------------|---------------|-----------------------------|
| | | | | Rate in figure | Rate in words | |
| 1 | Roadway Excavation in all types of soil by Manual Means as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer. | cum | 6.64 | | | |
| 2 | Providing, laying and levelling of Dry Stone Soling works in the foundation all complete. | cum | 0.25 | | | |
| 3 | Providing and laying of Plain/Reinforced Cement Concrete machine mixed of Crushed aggregate in Foundation including F2 finishing formworks, compaction, curing, testing and relevant lead etc complete as per Drawing and Technical Specifications. PCC Grade M 15 | cum | 0.25 | | | |

Khumbu Pasanglhamu Rural Municipality

Office of the Rural Municipal Executive

Chaurikharka, Solukhumbu

Bill of Quantity

Name of the Project : Mislung Namche Street Light Jadan

Location of the Project:- Khumbu Pasanglhamu R.M.-5, Mislung

F/Y:82/83

| S.N. | Description of work | Unit | Estimated Quantity | Rate (NRs.) excluding Vat | | Amount (NRs.) excluding Vat |
|------|---|------|--------------------|---------------------------|---------------|-----------------------------|
| | | | | Rate in figure | Rate in words | |
| 4 | Procurement of Solar Street Light 40W-12V DC with AutoDimming System , TX-XYD LifePO4 Battery 3.2 V /40 AH (3 Years Warrenty) Lighting Time 9 hrs-12 hrs Control Method PWM Controller Color Temperature Operating Temperature (-35° to 60°) (6000K- 6500k) Warrenty 2 Years | set | 14.00 | | | |
| 5 | Procurement of LED AC street Light(30/36W) with auto on off switch and auto dimming operation including all accessories and excluding installation | set | 21.00 | | | |
| 6 | Procurement of 25mm dia PN-12.5 HDPE pipe for grounding of wire for street Light | rm | 180.00 | | | |
| 7 | Procurement and installation of 7/22 copper wire for street light | roll | 2.00 | | | |

Khumbu Pasanglhamu Rural Municipality

Office of the Rural Municipal Executive

Chaurikharka, Solukhumbu

Bill of Quantity

FY:82/83

Name of the Project : Mislung Namche Street Light Jadan

Location of the Project:- Khumbu Pasanglhamu R.M.-5, Mislung

| S.N. | Description of work | Unit | Estimated Quantity | Rate (NRs.) excluding Vat | | Amount (NRs.) excluding Vat |
|--------------------|--|------|--------------------|---------------------------|---------------|-----------------------------|
| | | | | Rate in figure | Rate in words | |
| 8 | MS pole 6 m high with rust proof Hot Deep Galvanization dimension 65mm for buttom 3 m 50mm for top 2.5 m | Kg | 227.76 | | | |
| 9 | Transportation, Fixing, Installation etc of Street Light With Pannel | Ls | 1.00 | | | |
| Total amount | | | | | | |
| | | | | <u>VAT@13%</u> | | |
| Total Project Cost | | | | | | |

Total in words:
Name of firm
Address
Signature

Seal of Firm