



ॐ स्वस्ति नमो भगवते वासुदेवाय

खुम्बु पासडल्लिमा गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
चौरीखर्क, खोलीखुम्बु



प.सं.: ०८२/०८३
च.नं. १०२७


मिति:- २०८२/११/२८


बिषय : - दरभाउपत्र पेश गर्ने बारे ।

श्री सबै निर्माण ब्यावसायीहरु

यस गाउँपालिकाबाट चालु आ.व. २०८२/०८३ मा यसै पत्र साथ संलग्न BOQ मा उल्लिखित आइटमका कार्यहरु गर्नु पर्ने भएकाले उक्त कार्य त्यस फर्मबाट के, कति दर रेटमा उपलब्ध गराउन सकिन्छ? सात दिन भित्र यस कार्यालयमा दर भाउपत्र पेश गर्नु हुन अनुरोध छ ।

कामको विवरण	कार्यान्वयन हुने वडा	टोल
बुक्सा खानेपानी मर्मत एवं निर्माण		१ बुक्सा


०८२/११/२८
धन प्रसाद आचार्य
अधिकृत (छैटौं)


Khumbu Pasanglhamu Rural Municipality
 Office of the Rural Municipal Executive
 Chaukharka, Solukhumbu
 Biling, Solukhumbu
 कोशी प्रदेश

आयोजनाको नाम: बुक्सा खानेपानी मर्मत एवं निर्माण

स्थान: खु.पा.गा.पा वडा नं १, बुक्सा

आ.व: २०८२/८३

F/Y: 82/83

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
1	Earth work in Excavation for foundation and pipe trench (BMS) including 30m lead & 1.5m lift per m3	cum	20.59			
2	Dry Stone solling and Dry stone filling work in Floor foundation including & 1.5m lift per m3	cum	2.16			
3	P.C.C (1:3:6) work as per specification per m3	cum	1.86			
4	stone masonry wall work 1.5m lift per m3(1:6) cement Sand Mortar .	cum	0.88			
5	Reinforced Cement Concrete work in Beam, Slab, Superstructure etc.(1:1:5:3) m3	cum	4.48			
6	Rainforcement With cutting bending binding and placing in position for RCC work per MT	kg	610.30			
7	Supplying and fixing of 25*25*4 mm Size angle iron post at distance of 2m for fensing work all complete as per Instruction of Site engineer.	kg	26.28			
8	Supplying and Fabricating of 10 S.W.G. GI Chain Link of mesh Size 2"*2" all complete work as per instruction of site engineer.	sqm	30.00			
9	plaster in punning for interruption chamber (BPT) 12.5 thickness inner / outer part ratio (1:3)	sqm	72.78			

Name of Firm
Address
Signature

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
10	Earth back filling on floor and foundation of all kinds of soil as design drawing ,specification and instruction of site engineer.	cum	5.54			
11	Different types of Fittings and transoportations	0.00	0.00			
12	Inlet	0.00	0.00			
13	Brass Union 50mm	pcs	1.00			
14	G.I. Pipe (50mm)	m	1.00			
15	G.I. Elbow 50mm	pcs	2.00			
16	G.I. Socket 50mm	pcs	1.00			
17	Washout & Overflow	0.00	0.00			
18	G.I. Pipe 63mm (40cm long)	m	0.70			
19	G.I. Elbow (63mm)	pcs	4.00			
20	G.I. Pipe(63mm)	m	2.10			
21	G.I. Union (63mm)	pcs	2.00			
22	G.I. Nipple ((63mm)) 9""long	pcs	3.00			
23	G I Gate Valve (63mm)	pcs	2.00			
24	Fire hydrant	0.00	0.00			
25	G I pipe 80mm	m	0.80			
26	G I Elbow80mm	pcs	2.00			
27	G.I. Pipe 80mm	m	0.70			
28	G.I. Union (80mm)	pcs	1.00			
29	G I nipple (80mm") 9"long	pcs	3.00			
30	G. M Gate Valve (80mm)	pcs	1.00			
31	G.I. Unequal Tee (80mm x 15mm)	pcs	1.00			
32	G.I. flange 800 set	pcs	1.00			
33	G.I. Nipple (1/2") 9"long	pcs	1.00			
34	G.I. pipe (1/2")	m	0.30			
35	G.I. pipe1/2")	m	0.85			
36	G.I. Union (1/2")	pcs	1.00			
37	G.I. Elbow (1/2")	pcs	2.00			
38	G.I. pipe (1/2")	m	0.50			
39	G.I. Socket (1/2")	pcs	1.00			

Name of Firm
Address
Signature

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
40	G.I. Pipe (1/2")	m	1.56			
41	G.I. Tee (1/2")	pcs	1.00			
42	outlet water supply	0.00	0.00			
43	G I pipe (1 1/2")	m	0.70			
	G I Elbow(1 1/2")	pcs	2.00			
	G.I. Pipe (1 1/2")	m	0.70			
	G.I. Union (1 1/2")	pcs	1.00			
	G I nipple (1 1/2" (9" long)	pcs	3.00			
	G I Gate Valve (1 1/2")	pcs	1.00			
	G.I unequal Tee(1 1/2"x1 1/2"x1 1/2")	pcs	1.00			
	G.I. flange (1 1/2")	pcs	1.00			
	G.I. Nipple (1/2") 9"l ong	pcs	3.00			
	G.I. pipe (1/2")	m	0.30			
	G.L pipe1/2")	m	0.85			
	G.I. Union (1/2")	pcs	1.00			
	G.I. Elbow (1/2")	pcs	2.00			
	G.I. pipe (1/2")	m	0.50			
	G.I. Socket (1/2")	pcs	1.00			
	G.I. Pipe (1/2")	m	1.56			
	G.I tee	pcs	1.00			
	HDPE pipe 50 m	m	20.00			
	Transportation and installation , fitting for RVT	kg	75.00			
	VAT@13%					
	Total Project Cost					

Seal of Firm

Name of Firm
Address
Signature