



Khumbu Pasanglhamu Rural Municipality  
Office of the Rural Municipal Executive  
Chaurikharka, Solukhumbu  
Bill of Quantity



Name of the Project : Thesyo Street Light Nirman

Location of the Project:- Khumbu Pasanglhamu R.M.-5, Theso

F/Y:82/83

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
1	Roadway Excavation in all types of soil by Manual Means as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer.	cum	0.59			
2	Providing, laying and levelling of Dry Stone Soling works in the foundation all complete.	cum	0.23			
3	Providing and laying of Plain/Reinforced Cement Concrete machine mixed of Crushed aggregate in Foundation including F2 finishing formworks, compaction, curing , testing and relevant lead etc complete as per Drawing and Technical Specifications. PCC Grade M 15	cum	0.53			
4	Procurement of Solar Street Light 40W-12V DC with AutoDimming System , TX-XYD LifePO4 Battery 3.2 V /40 AH ( 3 Years Warrenty) Lighting Time 9 hrs-12 hrs Control Method PWM Controller Color Temperature Operating Temperature (-35° to 60°) (6000K-6500k) Warrenty 2 Years	set	13.00			

Khumbu Pasanglhamu Rural Municipality  
Office of the Rural Municipal Executive  
Chaurikharka, Solukhumbu  
Bill of Quantity



Name of the Project : Thesyo Street Light Nirman

Location of the Project:- Khumbu Pasanglhamu R.M.-5, Theso

F/Y:82/83

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
5	MS pole 6 m high with rust proof Hot Deep Galvanization dimension 65mm for buttom 3 m 50mm for top 2.5 m	Kg	211.49			
6	Transportation,Installation & Fittings	Ls	1.00			
	Sub Total					
	VAT@13%					
	Grand Total					

Total in words:  
Name of firm  
Address  
Signature

Seal of Firm