



ॐ नमो भगवते वासुदेवाय

खुम्बु पासाङल्हामु गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
चौरीखर्क, सोलुखुम्बु



प.सं.: ०८२/०८३
च.नं. ८१५

मिति:- २०८२/१०/२५



बिषय : - दरभाउपत्र पेश गर्ने बारे ।

श्री सबै निर्माण ब्यावसायीहरु

यस गाउँपालिकाबाट चालु आ.व. २०८२/०८३ मा यसै पत्र साथ संलग्न BOQ मा उल्लिखित आइटमका कार्यहरु गर्नु पर्ने भएकाले उक्त कार्य त्यस फर्मबाट के, कति दर रेटमा उपलब्ध गराउन सकिन्छ? सात दिन भित्र यस कार्यालयमा दर भाउपत्र पेश गर्नु हुन अनुरोध छ ।

कामको विवरण	कार्यान्वयन हुने वडा	टोल
डमातेड सिंचाई योजना	३	डमातेड


रोहित कटवाल
ईन्जिनियर
रोहित कटवाल
ईन्जिनियर (सातौं)

Khumbu Pasangshame Rural Municipality
Office of the Rural Municipal Executive
Chaurikharka, Solukhumbu
Bill of Quantity

मन्त्रालय
असिस्टन्ट कन्ट्रोलर
इन्जिनियर (सामग्री)

Name of the Project: डमतेङ सिन्याङ योजना
Location: kplrm-3, Namoteng

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
1	Earthwork pipe trench excavation work	Cum	186.03			
2	Back filling work for sewer pipe	Cum	139.52			
3	Providing, laying and levelling of Dry Stone Soling works in the foundation all complete.	Cum	1.67			
4	Providing and laying of dry Stone Masonry Work	cum	4.21			
5	Providing and laying of Reinforced Cement Concrete machined mixed of Grade M20 of aggregate for Foundation, sub-structure etc including F2 Finishing Formworks, compaction, curing, testing and Relevant lead etc complete as per Drawing and Technical Specifications. RCC Grade M 20 height up to 5m	Cum	3.81			
6	Providing and laying, fitting and placing un-coated Mild steel / HYSD reinforcement complete in foundation as per drawing and technical specification	mt	0.67			
7	C.I. tank cover locking types- Rectangular	0	0.00			
8	For collection chamber (18"x18")	set	1.00			

Khumbu Pasangthamu Rural Municipality
Office of the Rural Municipal Executive
Chauricharka, Solukhumbu
Bill of Quantity

Name of the Project: उमालेङ सिन्धुङ योजना
Location: kpirm-3, Namotang

[Signature]
राईस कटवाल
इन्जिनियर (सिती)

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
9	HDPE pipe of PN 12.5 as supply pipe	0	0.00			
10	32mm dia.(PN-12.5)	rm	1245.00			
11	40 mm dia.PN- 12.5	rm	25.00			
12	20 mm dia PN- 16	rm	100.00			
13	मान सामान उपलब्ध गरी 0.41 मी.मी. (२६ गेज हेपी) 65 के.जि. प्रति बण्डल सादा मि. जि. आई. मिट (बसला पाला) को छाता छाड्ने काम पुरा	sq.m.	4.12			
14	Various types of fitting and accessories	0	0.00			
15	For inlet	0	0.00			
16	Brass union with adopter (GI 25mm)	nos	1.00			
17	GI nipple medium class 9" long (25mm dia)	nos	2.00			
18	GI elbow 25mm	nos	3.00			
19	GI pipe threaded 25mm- Heavy duty	rm	2.00			
20	For outlet	0	0.00			
21	GI nipple medium class 5" long (40mm dia)	nos	1.00			
22	GI elbow 40mm	nos	2.00			
23	GI nipple medium class 9" long (40mm dia)	nos	2.00			
24	G.M. gate valve (40mm)	rm	1.00			
25	GI union (40mm)	nos	2.00			
26	For overflow	0	0.00			
27	GI nipple medium class 18" long (25mm dia)	nos	1.00			
28	GI elbow 25mm	nos	1.00			
29	For outlet	0	0.00			
30	GI nipple medium class 18" long (25mm dia)	nos	1.00			
31	GI elbow 25mm	nos	2.00			
32	G.M. gate valve (25mm)	rm	1.00			
33	For distribution	0	0.00			
34	G.M. gate valve (25mm)	rm	2.00			
35	GI nipple medium class 18" long (25mm dia)	nos	2.00			


रिशि कटवाल
 इन्जिनियर (सतौ)

Name of the Project: डमालेड सिन्पाङ योजना
 Location: kplrm-3, Namoteng

S.N.	Description of work	Unit	Estimated Quantity	Rate (NRs.) excluding Vat		Amount (NRs.) excluding Vat
				Rate in figure	Rate in words	
36	G.M. gate valve (25mm)	rm	7.00			
37	Brass union with adopter (GI 25mm)	nos	2.00			
38	Seal tape	pcs	10.00			
39	Saddle and craddle fittings for 32mm dia pipe to supply 20mm dia	set	8.00			
40	Total materials and jointing charge	job	1.00			
41	Transportation of fittings accessories	kg	50.00			
Sub Total						
VAT@13%						
Total Project Cost						

Total in words:
 Name of firm
 Address
 Signature

Seal of Firm